

JAN 21 1999

SCHOOLCRAFT COUNTY PEER GROUP APPROVED DATE 12/2/98 JOB

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: Schoolcraft (County), Located In, Corner Code #. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

SIGRID HEDBERG SCHOOLCRAFT CO. REGISTER 1P Page 1 of 1 LC 4/238 JLO Rec. Date 12/15/98 Time 14:20 REVENUE FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat 5. Private Claims

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 and an 'X' in row 3, column I.

Thomas P. O'Brien in a field survey on Dec. 11, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:


NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: I3 NW Corner Section 11, T41N - R16W Sept 10, 1845 - John Burt D.S. set post corner of sections 2,3,10 & 11 referenced by: Y. Pine 18 N5E 47 Spruce 5 S70W 15 May 6, 1981 - LCRC (L.1 Pg.260) by Thomas P. O'Brien P.S. indicates "Found old wood post, checks well with other corners in area, set County Mon." April 11, 1995 - LCRC (L.4 Pg 173) by Gerald W. Carlson P.S. indicates "Found a 3 1/4" diameter stamped aluminum County survey monument, 0.15' high at the top of a small rise @ S.W. corner of sand pit.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: I3 Dec. 11, 1998 - Thomas P. O'Brien P.S. recovered Schoolcraft County Monument stamped to identify. Existing witnesses verify corner location as found by Carlson 4/11/95.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: I3 Schoolcraft County Monument stamped to identify. Repainted blazes on NBT's and made measurements to the following references:

- 12" W. Pine - N67°W - 38.03'
16" R. Pine - N 6°E - 53.84'
8" W. Birch - S78°E - 18.69'
4" W. Pine - S19°W - 10.90'
Carsonite post - North - 1.0'



Signed by Thomas P. O'Brien

Date December 14, 1998

Surveyor's Michigan License No. 21274