

JAN 21 1999

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

SECTION

DATE 12/29/98

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SIGRID HEDBERG SCHOOLCRAFT CO. REGISTER 1P Page 1 of 1 LC 4/ 281 JLO Rec. Date 01/04/99 Time 13:16 REVENUE FEES: 9.00

Table with columns: Located in, Corner Code #, and rows for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat Private Claims

I, Thomas P. O'Brien in a field survey on 12/28, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13, containing numbers 1-36 and an 'X' in row 4, column H.

A. Description of original monument and accessories and/or subsequent restoration:

I4 1/4 corner corner common to sections 10 and 11 Sept. 11, 1845 John Burt, DS set qr. section post Tamarack 2 N68°W 50 Tamarack 3 N44°E 29

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

I4 Dec. 28, 1998 Thomas P. O'Brien, Ps reestablished corner by single proportionat measurement between I3 and I5. Set Schoolcraft County monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I4 Schoolcraft County monument stamped to identify. Established the following references which have been blazed, scribed, painted and tagged:

- 10" Cedar N48°W 7.11'
6" Cedar N59°E 30.47'
8" Cedar S12°E 10.32'
10" Cedar S38°W 37.84'
Carsonite Post North 1.0'



Signed by Thomas P. O'Brien Surveyor's Michigan License No. 21274

Date 12/31/98