

JAN 21 1999

SCHOOLCRAFT COUNTY
PEER GROUP APPROVED

DATE 12/2/98 LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T41N R 16W</u>	<u>I5</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/275
JLV Rec. Date 12/28/98 Time 15:29
REVENUE FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5									X				
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Thomas P. O'Brien in a field survey on Dec. 14 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I5 NW Corner Section 14, T41N - R16W
Sept. 11, 1845 - John Burt D.S. set post corner of sections
10, 11, 14 & 15 referenced by: Spruce 4 S46E 84 W.Pine 9 N21W 140

May 25, 1950 - Carl Christensen County Surveyor set 4' x 2" iron pipe with brass cap stamped C.C. from W. Pine 9" N21°W 140 links.

April 17, 1995 - LCRC (L.4 Pg.174) by Gerald W. Carlson P.S. indicates "Fd. a 2½" O.D. pipe with 2½" brass cap."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I5 Dec. 14, 1998 - Thomas P. O'Brien P.S. recovered 2" iron pipe with brass cap stamped 10, 11, 14 & 15 C.C. Corner falls in small marshy area. Fd. cedar post in poor condition. Existing BT's verify corner location as found by Carlson 4/17/95.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I5 4' x 2" iron pipe with brass cap stamped to identify. Repainted blazes on NBT's and made measurements to the following references:

- 22" W. Pine - S31°E - 76.30'
- 13" Cedar - S62°E - 46.31'
- 12" R. Pine - N80°W - 54.52'
- 8" Cedar - N 6°E - 40.64'
- Carsonite post - North - 1.0'



Signed by Thomas P. O'Brien

Date December 16, 1998

Surveyor's Michigan License No. 21274