

SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED

DATE 10/15/97

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &  
REMONUMENTATION

JAN 21 1998

For corners in

Schoolcraft

(County)

Located In:

Corner Code #

1. Public Land Survey

T 42N R 16W

K13

T 41N R 16W

K1

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

SECTION

Received & Filed this 9 day of  
Dec 1997 at 3:57 PM

Sigrid I. Hedberg  
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Thomas P.O'Brien, in a field survey on Oct. 28, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13											X		

A. Description of original monument and accessories and/or subsequent restoration:

K13 SW corner Section 36

Aug. 4, 1845 John Burt, DS set corner post  
Tamarack 7 N40E 16 do 7 N72W 11

June 19, 1978 Thomas P.O'Brien, PS found 1½" iron pipe at corner location.  
LCRC recorded in Liber 1, Page 182.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K13 Oct. 28, 1997 Thomas P.O'Brien, PS recovered a 1½" iron pipe. Found witnesses verify corner location. Replaced 1½" iron pipe with iron bar and OBRIEN 21274 cap in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K13 ½" iron bar with OBRIEN 21274 cap in monument box.

Witnesses:

- (FD) 14" Tamarack N40°E 28.95'
- (FD) 8" Maple S46°E 48.0'
- (FD) 8" Maple N58°W 71.10'
- NBT 10" Tamarack N5°E 38.55'
- NBT 10" Spruce S7°W 25.0'

*Thomas P. O'Brien*

Signed by Thomas P.O'Brien, PS

Surveyor's Michigan License No. 21274

Date Dec. 9, 1997

