

SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED  
DATE 12/2/98 JPB

SURVEY &  
REMONUMENTATION

JAN 21 1999

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A.

SECTION

For corners in

Schoolcraft  
(County)

Located In:

Corner Code #

STANLEY HEBBERG  
SCHOOLCRAFT CO. REGISTER 1P  
Page 1 of 1  
JLV Rec. Date 12/15/98 LC 4/ 236  
REVENUE FEES: Time 14:18  
9.00

1. Public Land Survey

T41NR 16W K5

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3			2		1
3													
4	7		8			9		10		11		12	
5											X		
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

Thomas P. O'Brien in a field survey on Dec. 9, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K5 NW Corner Section 13, T41N - R16W  
Sept. 10, 1845 - John Burt D.S. set post corner of sections 11, 12, 13 & 14  
referenced by: Spruce pine 8 N11W 76 Tamarack 4 S42½E 28  
Sept. 5, 1975 - LCRC (L.1 Pg.156) by Thomas P. O'Brien P.S. indicates  
"Found squared post and pipe in North edge of marsh area."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K5 Dec. 9, 1998 - Thomas P. O'Brien P.S. recovered 1½" iron pipe with squared post 1.0' North with existing witnesses. Reset iron pipe with Schoolcraft County Monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


K5 Schoolcraft County Monument stamped to identify. Repainted blazes on NBT's and made measurements to the following references:

- 18" W. Pine - N20°W - 18.60'
- 8" J. Pine - N16°E - 36.71'
- 18" W. Pine - N37°E - 55.20'
- 6" Spruce - N60°E - 31.35'
- Carsonite post - South - 1.0'

*Thomas P. O'Brien*

Signed by Thomas P. O'Brien

Surveyor's Michigan License No. 21274



Date December 14, 1998