

JAN 21 1999

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

DATE 12/2/98 LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Schoolcraft (County)

Located In:

Corner Code #

SIGRID HEDBERG SCHOOLCRAFT CO. REGISTER 1P Page 1 of 1 LC 4/246 JLO Rec. Date 12/15/98 Time 14:24 REVENUE FEES: 9.00

1. Public Land Survey

T41NR16W

M3 ✓

T41NR15W

A3

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

SURVEY & REMONUMENTATION

MAR 03 1999

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat

SECTION

5. Private Claims

Grid table with columns A-M and rows 1-13. Cell 3, L contains an 'X'.

Thomas P. O'Brien in a field survey on Dec. 3, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M3 NE Corner Section 12, T41N - R16W 1845 - John Burt D.S. set post corner of sections 1 & 12 T41N - R16W and sections 6 & 7 T41N - R15W, referenced by: Cedar 14 N 82 W 34 Cedar 12 S 23 W 13

April 7, 1995 - LCRC (L.4 Pg. 171) by Gerald W. Carlson P.S. 24589 indicates he "Found 2" O.D. iron pipe, 0.7' below gravel surface, and 2.2' North of North edge rail of R.R. siding."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M3 Dec. 3, 1998 - Thomas P. O'Brien P.S. recovered a 2" iron pipe with double headed nail 2.2' North of North edge of rail. Witnesses found verify corner location as found by Gerald W. Carlson, April 7, 1995. Reset iron pipe with Schoolcraft County Monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M3 Schoolcraft County Monument stamped to identify. Repainted blazes on NBT's and made measurements to the following references:

- (Fd.) 10" W. Pine - N21°W - 90.01'
(Fd.) 8" W. Pine - N11°W - 71.84'
(Fd.) 8" Aspen - N14°E - 66.16' (Poor condition)
(Fd.) 6" Tamarack - N43°W - 86.65'
NBT 5" Cedar - N16°E - 74.93'

Signature of Thomas P. O'Brien

Signed by Thomas P. O'Brien

Date December 6, 1998

Surveyor's Michigan License No. 21274

