

**SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED**

DATE 12/2/98 00B LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &  
REMONUMENTATION

JAN 21 1999

For corners in  
Schoolcraft Located In: Corner Code #  
(County)

1. Public Land Survey T 41N R 17W A-8  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_
2. Property Controlling S \_\_\_ T \_\_\_ R \_\_\_  
in Section S \_\_\_ T \_\_\_ R \_\_\_  
3. Miscellaneous S \_\_\_ T \_\_\_ R \_\_\_  
Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_

SIGRID HEDBERG 1P  
SCHOOLCRAFT CO. REGISTER  
Page 1 of 1 LC 4/203  
JLO Rec. Date 12/03/98 Time 14:17  
REVENUE FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, GERALD W. CARLSON, in a field survey on February 24, 19 98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**  
A-8: West Quarter corner Section 19

1845: John Burt's original survey notes describe the corner monument as a set 1/4 Section post (no corner monument description given) referenced by:  
5: Hemlock S 57°W 42 L 7" Hemlock N 80°W 38 L

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**  
A-8:1998: No original corner evidence found. The corner was re-established equidistant and on line between the found Northeast and Southeast corners of Section 24. The distances North and South are 2658.60'. A Tom O'Brien 1/2" iron w/cap No. 21274 was found 6.60' Southwest of this position and upon consultation with Tom it was determined this 1/2" iron was set in the wrong position and was pulled out per Tom's concurrence.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
A-8: 1998: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Delta County Survey Monument stamped to identify the corner. Established references with painted blazes and dh nails in:

- 12" Maple N 48°E 19.00' (O'Brien NBT)
- 8" Cedar S 51°E 53.80' (O'Brien NBT)
- 14" Maple S 42°W 80.65' (O'Brien NBT)
- 8" Maple S 78°W 27.46'

Green steel fence post w/ Yellow Survey Marker sign N 74°E, 1.54'

Centerline North-South road West, 20.25'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.



Signed by Gerald W. Carlson Date 4-30-98  
Surveyor's Michigan License No. 24589