

**HOOLCRAFT COUNTY
 SURVEY GROUP APPROVED**

**SURVEY &
 REMONUMENTATION**

DATE 12/2/98 JOB **LAND CORNER RECORDATION CERTIFICATE**
 Filing Requirement of Act 74, Mich. P.A. 1970

JAN 21 1999

corners in
Schoolcraft Located In: Corner Code #
 (County)

SECTION

Public Land Survey T 41N R 17W A-12
 T ___ R ___
 T ___ R ___
 T ___ R ___
 Property Controlling S ___ T ___ R ___ **SIGRID HEDBERG**
 Section S ___ T ___ R ___ **SCHOOLCRAFT CO. REGISTER**
 Miscellaneous S ___ T ___ R ___ **Page 1 of 1**
 Property in Sec. S ___ T ___ R ___ **JLV Rec. Date 12/03/98 Time 14:19**
REVENUE FEES: 9.00

1P
LC 4/204
Register of Deeds Stamp & File Number

Plot No. _____, Recorded Plat _____
 Private Claims _____

GERALD W. CARLSON, in a field survey on February 25, 1998, hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner mentioned in lines 1 and 2 above were in conformance with regulations and rules more as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; re-established, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

West Quarter Corner Section 31

John Burt's original Township survey notes describe the corner monument as a 1/4 post (no corner monument description given) referenced by:
 Marack S 53°W 87 L 4" Cedar N 62°W 53 L

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998: No original corner evidence found. The corner was re-established equidistant and on line between the found northeast and east corners of Section 31. The Distances North and South are 2644.76'

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1998: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Delta County Survey Monument used to identify the corner. Established references using painted blazes and dh nails in:
 Iron S 25°W 71.11' 12" Cedar N 18°W 86.92'
 Iron N 42°E 42.33' 6" Cedar S 40°E 21.58'
 Steel fence post w/ Yellow Survey Marker sign N 60°E, 2.90'

Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, stamped B.T. Tags affixed.



by Gerald W. Carlson

Date 4-30-98

Surveyor's Michigan License No. 24589