

SCHOOLCRAFT COUNTY
PEER GROUP APPROVED

SURVEY &
REMONUMENTATION

DATE 10/21/98 JOB LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 21 1999

For corners in

SECTION

Schoolcraft Located In: Corner Code #
(County)

1. Public Land Survey T41NR16W A-1
T41NR17W M-1
T42NR16W A-13
T42NR17W M-13
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/206
JLO Rec. Date 12/03/98 Time 14:24
REVENUE FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien in a field survey on Oct. 22, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- A1 NW corner Section 6, T41N - R16W
Aug. 4, 1845 - John Burt D.S. set post corner of Towns 41 and 42 North and between Ranges 16 and 17 West, referenced by:
Beech 8 S 76 W 33 Beech 14 N 47 W 37
June 20, 1979 - Thomas P. O'Brien P.S. recovered a concrete monument, set at SW Corner of Assessor's Plat of Ash Resort area by M.P. Davis LS 16926.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A1 Oct. 22, 1998 - Thomas P. O'Brien P.S. recovered concrete monument at SW Corner of Assessor's Plat of Ash Resort area.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A1 Concrete Monument, established the following references which are blazed, scribed, painted and tagged:

- (Fd.) 10" Maple - S85°W - 20.82'
(Fd.) 12" Maple - N71°W - 8.95'
22" Maple - N38°E - 100.28'
12" Maple - S70°E - 75.37'
4 X 4 treated scribed post - N45°W - 0.30'

Thomas P. O'Brien

Signed by Thomas P. O'Brien

Date November 27, 1998

Surveyor's Michigan License No. 21274

