

JAN 21 1999

SECTION

SCHOOLCRAFT COUNTY
PEER GROUP APPROVED

DATE 10/21/98 JOB

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T41NR16W	A-3
	T41NR17W	M-3
	T___R___	_____
	T___R___	_____
2. Property Controlling in Section	S___T___R___	_____
	S___T___R___	_____
3. Miscellaneous Property in Sec.	S___T___R___	_____
	S___T___R___	_____

SIGRID HEDBERG
SCHOOLCRAFT CO. REGISTER 1P
Page 1 of 1 LC 4/ 208
JLV Rec. Date 12/03/98 Time 14:25
REVENUE FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien in a field survey on Oct. 22, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3	X												
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

A3 NW Corner Section 7, T41N - R16W
July 29, 1845 - John Burt D.S. set post corner of sections 6 and 7,
T41N - R16W and sections 1 and 12, T41N - R17W, referenced by:
Y. Birch 8 S 50 W 17 Y. Birch 8 N 73 W 21

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A3 Oct. 22, 1998 - Thomas P. O'Brien P.S. recovered a 3/4" iron pipe with top bent 3.0' below gravel surface on East shoulder of Co. Road 455. Reset 3/4" iron pipe with Schoolcraft County Monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A3 Schoolcraft County Monument stamped to identify. Established the following references which are blazed, scribed, painted and tagged:

- NBT 12" Maple - N58°E - 50.79'
- NBT 10" Maple - S38°E - 65.48'
- NBT 10" Maple - S74°W - 105.78'
- NBT 8" Maple - N35°W - 120.82'
- Centerline County Rd. 455 - West - 15.50'
- Carsonite post - East - 20.0'



Signed by Thomas P. O'Brien
Surveyor's Michigan License No. 21274

Date November 29, 1998