

JAN 21 1999

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

DATE 10/21/98 JOB LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Table with columns: Schoolcraft (County), Located in, Corner Code #. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

SIGRID HEDBERG SCHOOLCRAFT CO. REGISTER 1P Page 1 of 1 JLO Rec. Date 12/03/98 LC 4/216 REVENUE FEES: Time 14:28 9.00

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat 5. Private Claims

I, Thomas P. O'Brien in a field survey on Oct. 26, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 1-13. Contains numerical values for each cell.

A. Description of original monument and accessories and/or subsequent restoration:

All NW Corner Section 31, T41N - R16W July 29, 1845 - John Burt D.S. set post corner common to sections 30 & 31 T41N - R16W and sections 25 and 36, T41N - R17W. Referenced by: Y. Birch 12 S 72 W 15 Fir 5 N 62 W 26

July 1983 - William F. Bowman L.S. 28406 " Re-established corner by proportionate measure on line between A-7 & A-13, and set a 1/2" rebar & I.D.cap"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

All Oct. 26, 1998 - Thomas P. O'Brien P.S. recovered a 1/2" I.B. with cap #28406, found NBT's check well with Bowman L.C.R.C. (L.1 Pg.355 L.S.28406). Replaced I.B. with Schoolcraft County Monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

All Schoolcraft County Monument stamped to identify. Repainted blazes on NBT's and made measurements to the following references:

- (Fd.) 6" Balsam - N50°E - 43.40'
(Fd.) 10" Aspen - S35°E - 27.0' (Fair cond.)
(Fd.) 8" Maple - S65°W - 24.60'
NBT 4" Cedar - N3°W - 19.42'
NBT 12" W.Pine - S2°W - 162.78'
C/L East and West road - South - 48'
Carsonite post - North - 1.0'

Signed by Thomas P. O'Brien

Date November 29, 1998

Surveyor's Michigan License No. 21274

