

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Schoolcraft

(County)

Located In:

Corner Code #

- |                                       |             |                           |          |
|---------------------------------------|-------------|---------------------------|----------|
| 1. Public Land Survey                 | T           | R                         | _____    |
|                                       | T           | R                         | _____    |
|                                       | T           | R                         | _____    |
|                                       | T           | R                         | _____    |
| 2. Property Controlling<br>in Section | S <u>31</u> | T <u>41N</u> R <u>17W</u> | <u>3</u> |
|                                       | S           | T                         | R        |
| 3. Miscellaneous<br>Property in Sec.  | S           | T                         | R        |
|                                       | S           | T                         | R        |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Jun 03 2003

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:  
 (3-Sec. 31) North 1/16 corner between Sections 31 T41N-R17W and 36 T41N-R18W. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 (3-Sec. 31) Found a 5/8" dia. rebar 0.04' N and 0.04' E of the midpoint between Section and Quarter corners north and south and accepted same. The corner lies approximately 15' east of a road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 (3) Set plastic cap "MICH DNR PS 33986" on found 5/8" dia. rebar. Blazed, scribed, and set measuring nails in:  
 5" Balsam S42E 15.65' "N1/16 BT"  
 5" Balsam S12W 17.75' do  
 6" Cedar S31E 52.8' do  
 10" W. Birch S82W 71.4' do  
 Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 6/16/03