

JAN 21 1999

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

SECTION

DATE 12/2/98 LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft (County)

Located In:

Corner Code #

SIGRID HEDBERG SCHOOLCRAFT CO. REGISTER 1P Page 1 of 1 LC 4/245 JLV Rec. Date 12/15/98 Time 14:24 REVENUE FEES: 9.00

- 1. Public Land Survey T41NR16W T41NR15W T R T R S T R S T R S T R

M4 A4

SURVEY & REMONUMENTATION

MAR 03 1999

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat SECTION 5. Private Claims

Grid table with columns A-L and rows 1-13. Cell (4,12) is marked with an X.

Thomas P. O'Brien in a field survey on Dec. 3, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M4 E 1/2 Corner Section 12, T41N - R16W 1845 - John Burt D.S. set qr. section post common to section 12 T41N - R16W and section 7 T41N - R15W, referenced by: Hemlock 7 N52W 22 Hemlock 8 S59W 5

June 22, 1989 - LCRC (L.2 Pg. 218) by Gerald W. Carlson P.S. 24589 indicates he " Found 1/2" rered with L.L.S. cap no. 28406 and 5/8" rered along side inside ball diamond fence."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M4 Dec. 3, 1998 - Thomas P. O'Brien P.S. recovered 1/2" rered with RLS cap 28406 and 5/8" rod alongside. Accepted 1/2" rered with 28406 cap, existing witnesses found verify corner location as found by Gerald W. Carlson P.S. on June 22, 1989. Replaced 1/2" rered with Schoolcraft County Monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M4 Schoolcraft County Monument stamped to identify. Made measurements to the following references:

- (Fd.) SW corner fence post of ball field - S37°W - 36.0' (Fd.) 4th post North of corner post - N45°W-1.82' (Fd.) 7th post North of corner post - N31°E - 31.23' (Fd.) 3rd post East of corner post - S8°E - 53.24' Carsonite post - West - 2.0'

Thomas P. O'Brien signature

Signed by Thomas P. O'Brien

Date December 6, 1998

Surveyor's Michigan License No. 21274

