

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

DATE 11/8/99 TPB

JAN 25 2000

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION _____

For corners in

Schoolcraft

(County)

Located In:

Corner Code #

1. Public Land Survey

T 41 N R 15 W

C2

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____

T _____ R _____

S _____

T _____ R _____

3. Miscellaneous
Property in Sec.

S _____

T _____ R _____

S _____

T _____ R _____

SIGRID HEDBERG
SCHOOLCRAFT CO. REGISTER 1P
Page 1 of 1 LC 4/300
JLO Date 12/22/1999 Time 13:52:59
RECORDING FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien in a field survey on 12/13, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	X	5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
Sept. 9, 1845 J. Burt, DS Set qr. sec. post Cedar 5 N89E 10 W. Birch 5 S70W 8

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Dec. 13, 1999 Thomas P. O'Brien, PS reestablished corner by proportionate measurement between C1 and C3.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Schoolcraft County monument stamped to identify

Witnesses:

4" Cedar S18°E 57.6'

Carsonite Post North 1.0'

Carsonite Post East 20.0'

Carsonite Post West 20.0'

Centerline NandS grade 25' East

Corner falls in open marsh area.

Thomas P. O'Brien
Thomas P. O'Brien



Signed by _____

Date 12/16/99

Surveyor's Michigan License No. 21274