

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

RECORDED

JAN 25 2000

DATE 11/8/99 JOB LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION _____

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T 41N R 15W	C4
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

SIGRID HEDBERG
SCHOOLCRAFT CO. REGISTER 1P
Page 1 of 1
JLO Date 12/22/1999 LC 4/301
RECORDING FEES: Time 13:53:13
9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien, in a field survey on Nov. 22, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7	X	8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
Sept. 8, 1999 J. Burt, DS W. Birch 12 qr. corner Spruce 5 N41W 16


May 11, 1978 Douglas W. Hooth, RLS found 1/2" iron pipe with one RLS reference marker 21274.
Placed 1/2" copper clad rod w/ brass cap RLS 16944

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Nov. 22, 1999 Thomas P. O'Brien, PS found 1/2" copper clad rod w/ RLS 16944 cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1/2" copper clad rod w/ RLS 16944 cap
- Witnesses:
- SW Corner of House N25°W 50.60'
- SW Corner of Cafe N60°E 46.46'
- NE Corner Sign Base S15°W 26.35'
- 8" White Pine N76°W 42.97'
- Carsonite Post West 15.0'



Signed by Thomas P. O'Brien
Thomas P. O'Brien

Date Dec. 16, 1999

Surveyor's Michigan License No. 21274