

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

500-1000
011-1000

JAN 30 1996

COMMISSION

DATE May 12, 1995 **LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42 N</u> R <u>15 W</u>	D-13
	T <u>41 N</u> R <u>15 W</u>	D-1 ✓
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Received & Filed this 6 day of Dec 19 95 at 11:40 A M
Sigrid I. Hedberg
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Thomas P. O'Brien, in a field survey on Oct. 6, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
D-13 (South 1/4 Corner Sec. 32)
Aug. 6, 1845 John Burt D.S. set qr. section post.
Hemlock 18 N6W 16 W. Pine 22 N71E 13

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
D-13 Dec. 20, 1994 Thomas P. O'Brien, PS recovered a 3/8" iron bar w/RLS #21274 cap set over the center of a 1 1/2" iron pipe 16" below road surface. The corner position as recovered has been used in previous surveys of record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
D-13 3/8" iron bar w/RLS 21274 cap set in monument box.
Witnesses:
Power Pole N47°E 34.25'
12" Maple S44°E 83.9'
6" Maple S26°W 96.62'
8" Maple N87°W 76.7'



Signed by Thomas P. O'Brien, PS Date Dec. 4, 1995

Surveyor's Michigan License No. 21274