

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

RECORDED

JAN 25 2000

SECTION

DATE 11/8/99 JPB

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Schoolcraft</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 41N R 15W	D3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

SIGRID HEDBERG
SCHOOLCRAFT CO. REGISTER 1P
Page 1 of 1
JLO Date 12/22/1999 LC 4/307
RECORDING FEES: Time 13:55:06 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien, in a field survey on 12/14, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3				X									
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:


Sept. 8, 1845 J. Burt, DS Set qr. section post Spruce 8 S30W 23 Do 5 N57E 24

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Dec. 14, 1999 Thomas P. O'Brien, PS reestablished corner by proportionate measurement C3 to E3.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Schoolcraft County monument stamped to identify.
Witnesses:
Carsonite Post North 20.0'
Carsonite Post South 20.0'
Carsonite Post East 20.0'
Carsonite Post West 20.0'
Corner falls in open marsh.



Signed by Thomas P. O'Brien
Surveyor's Michigan License No. 21274

Date 12/16/99