

# SCHOOLCRAFT COUNTY PEER GROUP APPROVED

FILED IN REGISTER

JAN 23 2000

DATE 11/8/99 <sup>JOB</sup> LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION \_\_\_\_\_

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T41N R15W	E2
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

SIGRID HEDBERG 1P  
SCHOOLCRAFT CO. REGISTER  
Page 1 of 1 LC 4/306  
JLO Date 12/22/1999 Time 13:54:45  
RECORDING FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Thomas P. O'Brien, in a field survey on 12/13, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5	X	4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Sept. 9, 1845 J. Burt, DS set qr. sec. post Fir 6 S9E 8 W Birch 10 N26W 18

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Dec. 13, 1999 Thomas P. O'Brien, PS reestablished corner by proportionate measurement E1 to E3. Corner falls in downed E-W fence line in West track of dirt trail road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Schoolcraft County monument stamped to identify.  
Witnesses:  
4" Red Pine N33°W 48.15'  
16" White Pine West 61.65'  
6" Red Pine S36°W 72.8'  
Power Pole S27°E 115.6'  
Carsonite Post West 5.0'



Signed by Thomas P. O'Brien  
Surveyor's Michigan License No. 21274

Date 12/16/99