

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

JAN 30 1996
COMMISSION

DATE May 12, 1995 **LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Schoolcraft</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>42 N</u> R <u>15 W</u>	<u>F-13</u>
	T <u>41 N</u> R <u>15 W</u>	<u>F-1</u> ✓
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Received & Filed this 6th day of
Dec 1995 at 11:38 A.M
Sigrid I. Hedberg
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Thomas P. O'Brien, in a field survey on Oct. 6, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-13 (South 1/4 Corner Sec. 33)
Aug. 6, 1845 John Burt D.S. set qr. section post.
Maple 12 N64W 38 do 7 N71E 42

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13 Aug. 5, 1976 Thomas P. O'Brien, RLS set 1/2" iron bar w/RLS#21274 cap" by single proportion between E-1 & M-1." Liber 1, Page 160.

Sept. 29, 1994 Thomas P. O'Brien, PS recovered iron bar w/illegible cap .30' below road surface. Bearing trees verify corner to be at same position as on Aug. 5, 1976. Road construction removed iron bar set Aug. 5, 1976.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13
3/4" iron bar set in monument box.
Witnesses:
10" Maple N33°W 81.95'
4" Cedar N17°E 87.25'
Power Pole S32°W 52.67'
Power Pole S23°W 75.25'



Signed by Thomas P. O'Brien, PS Date Dec. 4, 1995
Surveyor's Michigan License No. 21274