

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

JAN 25 2000

SECTION

DATE 11/8/99

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1999

For corners in

SIGRID HEDBERG
SCHOOLCRAFT CO. REGISTER 1P
Page 1 of 1
JLV Date 12/22/1999 LC 4/290
RECORDING FEES: Time 13:46:22
9.00

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>41</u> N R <u>15</u> W	G4
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien, in a field survey on 12/18, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			1
3													
4	7			8			9	X	10		11		12
5													
6	18			17			16			15			13
7													
8	19			20			21			22			24
9													
10	30			29			28			27			25
11													
12	31			32			33			34			36
13													

A. Description of original monument and accessories and/or subsequent restoration:

Sept. 8, 1845 J. Burt, DS set qr. section post Hemlock 6 S18½W 8 Spruce 4 S84E 35
May 6, 1975 Thomas P. O'Brien, PS found 3/4" iron bar and blazed cedar w/tag.
1979 Schoolcraft County Surveyor reset 3/4" iron bar w/Schoolcraft County monument.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Dec. 18, 1999 Thomas P. O'Brien, PS found Schoolcraft County monument and witnesses from 1975 LCRC. Witnesses verify corner position. Added witness and post.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Schoolcraft County monument stamped to identify.
Witnesses:
6" Cedar SOUTH 21.55'
6" Cedar N41°E 5.9'
14" Cedar Stub N70°W 20.5 (Above mentioned Cedar w/tag)
4" Cedar S56°E 10.85'
Carsonite Post NORTH 1.0'



Signed by Thomas P. O'Brien
Surveyor's Michigan License No. 21274

Date Dec. 22, 1999