

**SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED**

**DATE** May 12, 1995 **LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 30 1996  
COMMISSION

For corners in

|   |                             |               |
|---|-----------------------------|---------------|
| <u>Schoolcraft</u><br><small>(County)</small> | Located In:                 | Corner Code # |
| 1. Public Land Survey                         | T <u>42 N</u> R <u>15 W</u> | <u>H-13</u>   |
|   | T <u>41 N</u> R <u>15 W</u> | <u>H-1</u> ✓  |
|   | T _____ R _____             | _____         |
|   | T _____ R _____             | _____         |
| 2. Property Controlling in Section            | S _____ T _____ R _____     | _____         |
|   | S _____ T _____ R _____     | _____         |
| 3. Miscellaneous Property in Sec.             | S _____ T _____ R _____     | _____         |
|   | S _____ T _____ R _____     | _____         |

Received & Filed this 6 day of Dec. 1995 at 11:43 A M  
Sigrid I. Hedberg  
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

I, Thomas P. O'Brien, in a field survey on Nov. 6, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

H-13 (South 1/4 Corner Sec. 34)  
Aug. 6, 1845 John Burt D.S. set qr. section post.  
W. Birch 5 N31W 43 B. Ash 6 N51E 58

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 June 21, 1977 Thomas P. O'Brien, RLS set iron bar on line at single proportion.  
June 30, 1983 Donald R. Schofield, RLS recovered "iron with cap number 21274 along with bearing tree with a metal plate of county surveyor.  
Aug. 31, 1994 Gary E. Koepke, RLS recovered "1/2" iron with remains of plastic PS cap. Replaced found iron with 1/2" x 24" iron w/M.D.O.T. #26458 cap."  
Oct. 17, 1994 Thomas P. O'Brien, PS recovered 1/2" iron bar with plastic PS cap M.D.O.T. #26458.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13  
1 1/2" iron bar in monument box.  
Witnesses:  
Power Pole N45°E 89.46' Power Pole S60°E 67.29'  
18" Maple S25°W 77.85' 18" Maple (dead) S29°W 75.56'



Signed by Thomas P. O'Brien Thomas P. O'Brien, PS Date Dec. 4, 1995

Surveyor's Michigan License No. 21274