

NOV 2 1996

COMMISSION

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

DATE 7/12/96 LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft (County) Located in: Corner Code #
1. Public Land Survey T 42 N R 15 W T 41 N R 15 W I-13 I-1
2. Property Controlling in Section S T R S T R S T R S T R
3. Miscellaneous Property in Sec. S T R S T R

Received & Filed this 8th day of October 1996 at 11:33 A M

Sigrid I. Hedberg Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 and a small 'X' mark at row 12, column J.

Thomas P. O'Brien in a field survey on August 13, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-13 (S.E. Corner Sec. 34)
Aug. 6, 1845 John Burt D.S. set corner post.
W. Birch 10 N73W 19 Hemlock 9 N68E 33
Sept. 9/45 John Burt D.S. South between sections 2&3
Hemlock 10 S73W 12 do 7 S65E 16

SURVEY & REMONUMENTATION

DEC 16 1996

COMMISSION


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13 June 30, 1983 Donald R. Schofield R.L.S. 25871 re-established corner by extension of line controlled by G-13 and H-13.
August 13, 1996 Thomas P. O'Brien P.S. re-established corner by single proportionate measurement between H-13 and J-13. No Evidence of Schofield corner recovered.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 Set Schoolcraft County Monument stamped to identify.

- Witnesses: 8" Cedar - S48°W - 49.90'
10" Maple - N32°W - 150.40'
Power Pole - N60°E - 90.38'
2" Cedar - S50°E - 29.10'
4" Cedar Post - N4°E - 30.0'



Signed by Thomas P. O'Brien Date August 13, 1996

Surveyor's Michigan License No. 21274