

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

DATE 11/8/99 JOB

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

JAN 25 2000

SECTION _____

For corners in

Schoolcraft

(County)

Located in:

Corner Code #

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/312
JLO Date 12/22/1999 Time 14:00:53
RECORDING FEES: 9.00

- | | | |
|------------------------------------|-----------------------------|-----------|
| 1. Public Land Survey | T <u>41</u> N R <u>15</u> W | <u>I3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien in a field survey on 11/22, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3									X				
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- Sept. 7, 1845 J. Burt, DS set post corner of Sections 2,3,10,11 Y. Birch 16 S46E 24 Do 15 N56W 50
- March 8, 1977 Thomas P. O'Brien, PS found iron in centerline US-2.
- May 11, 1978 Douglas W. Hooth, RLS found iron pin w/RLS 21274 cap. Set monument box.
- Oct. 5, 1994 Gary E. Koepke, PS found a boat spike in monument box and witnesses from 1978 LCRC. Accepted corner position and added witnesses.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Nov. 22, 1999 Thomas P. O'Brien, PS found a boat spike in monument box and witnesses from 1994 LCRC.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Boat spike in monument box 24.6' North of centerline US-2 and 9.5' West of centerline of Hubble Road.
- Witnesses:
- Power Pole N35°E 66.12'
- Power Pole S5°W 94.98'
- 16" Red Pine S45°W 121.77'
- 18" Red Pine N30°W 107.20'
- Carsonite Post S6°W 90.0'

Thomas P. O'Brien

Signed by Thomas P. O'Brien
Surveyor's Michigan License No. 21274

Date 12/16/99

