

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

RECORDED

JAN 25 2000

DATE 11/8/99 JPB LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Schoolcraft (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>41N</u> R <u>15W</u>	<u>I4</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/291
JLO Date 12/22/1999 Time 13:49:24
RECORDING FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien in a field survey on 12/20, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10	X	11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Sept. 7, 1845 J. Burt, DS set qr. sec. post Cedar 7 N48E 9 W. Birch 4 S48W 13

May 11, 1978 Douglas W. Hooth, RLS found axle shaft on old fence line from distance on Michigan Dept. State Hwys. 1939 plans. Placed RLS cap 16944 on top of axle shaft on fence line.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Dec. 20, 1999 Thomas P. O'Brien, PS found axle shaft w/RLS 16944 cap on old fence line. Recorded witnesses verify corner position. Reset axle shaft w/Schoolcraft County monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Schoolcraft County monument

Witnesses:

5" Balsam S80°E 13.85'

6" Y. Birch N15°E 17.45'

4" Y. Birch N60°W 6.42'

4" Y. Birch S45°W 10.52'

Carsonite Post North 1.0'



Thomas P. O'Brien

Signed by Thomas P. O'Brien

Date Dec. 22, 1999

Surveyor's Michigan License No. 21274