

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

DATE 7/12/96 **LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

NOV 21 1996
COMMISSION

For corners in

Schoolcraft (County) Located In: Corner Code ##

1. Public Land Survey T 42 N R 15 W J-13
T 41 N R 15 W J-1

2. Property Controlling in Section S ___ T ___ R ___

3. Miscellaneous Property in Sec. S ___ T ___ R ___

Received & Filed this 8th day of October 1996 at 11:34 A M

Sigrid I. Hedberg
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Thomas P. O'Brien, in a field survey on August 13, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-13 (South 1/4 Corner Sec. 35)
Aug. 6, 1845 John Burt D.S. set qr. section post.
Y. Birch 8 N73W 19 do 7 N2½E 15

SURVEY &
REMONUMENTATION
DEC 16 1996
COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13 Nov. 28, 1979 Thomas P.O'Brien, RLS set Schoolcraft County Monument on "Township line by proportionate measure."

Dec. 29, 1993 Thomas P.O'Brien, PS recovered Schoolcraft Co. Mon. as set by Thomas P.O'Brien.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13 Found Schoolcraft County Monument stamped to identify.

Witnesses: 6" Maple - N32°W - 146.25'
5" Maple - N4°W - 90.71'
5" Maple - N27°E - 59.22'
Fd.8" Birch - N25°W - 54.20' Dead
Fd.8" Birch - N30°E - 63.50' Dead
Set4" Cedar Post - S4°W - 15.0'



Signed by Thomas P. O'Brien Date August 13, 1996
Surveyor's Michigan License No. 21274