

**SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED**

JAN 6 5 2000

SECTION

DATE 11/8/99 JOB LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft  
(County)

Located In:

Corner Code #

SIGRID HEDBERG 1P  
SCHOOLCRAFT CO. REGISTER  
Page 1 of 1 LC 4/310  
JLV Date 12/22/1999 Time 13:55:47  
RECORDING FEES: 9.00

- |                                    |   |             |
|------------------------------------|---|-------------|
| 1. Public Land Survey              | T <u>41N</u> R <u>15W</u>                 | <u>K2</u>   |
|                                    | T <u>    </u> R <u>    </u>               | <u>    </u> |
|                                    | T <u>    </u> R <u>    </u>               | <u>    </u> |
|                                    | T <u>    </u> R <u>    </u>               | <u>    </u> |
| 2. Property Controlling in Section | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |
|                                    | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |
| 3. Miscellaneous Property in Sec.  | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |
|                                    | S <u>    </u> T <u>    </u> R <u>    </u> | <u>    </u> |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Thomas P. O'Brien in a field survey on 12/13, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2	X	1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Sept.7, 1845 J. Burt, DS set qr. sec. post Beech 7 S21W 5 Do 5 S84E 22  
August 28, 1906 Eugene H. Ford, County Surveyor notes iron stake w/witnesses in Liber 1 Record of Surveys Page 70.  
Feb.22, 1978 Thomas P. O'Brien, PS found 1/2" iron bar and added witnesses.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Dec.13, 1999 Thomas P. O'Brien, PS found 1/2" smooth iron bar and reset with Schoolcraft County monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Schoolcraft County monument.  
Witnesses:  
20" Maple N45°E 51.85'  
20" Red Pine S45°W 39.20'  
24" Red Pine N86°W 31.40'  
911 Sign Post N8°E 32.20'  
Carsonite Post West 20.0'



Signed by Thomas P. O'Brien  
Surveyor's Michigan License No. 21274

Date 12/16/99