

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

RE...

JAN 25 2000

DATE 11/8/99 JOB LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>41N</u> R <u>15W</u>	L3
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/296
JLQ Date 12/22/1999 Time 13:51:22
RECORDING FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien, in a field survey on 12/14, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														
2	6			5			4			3			2	1
3														
4	7			8			9			10			11	12
5														
6	10			17			16			15			14	13
7														
8	19			20			21			22			23	24
9														
10	30			29			28			27			26	25
11														
12	31			32			33			34			35	36
13														

A. Description of original monument and accessories and/or subsequent restoration:

Sept 7, 1845 J. Burt, DS Set qr. section post Hemlock 14 S58W 7 Do 8 N25½E 11

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 31, 1987 Ferguson & Chamberlain Associates, Inc reestablished corner by proportionate measurement M3 to K3.

Dec. 14, 1999 Thomas P. O'Brien, PS replaced Ferguson & Chamberlain iron bar with Schoolcraft County monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L3 Schoolcraft County monument

Witnesses:

6" Spruce N36°W 10.10'

8" Spruce S61°W 6.93'

8" Twin Maple N29°E 45.95'

18" White Pine N74°E 28.05'



Signed by Thomas P. O'Brien

Date 12/16/99

Surveyor's Michigan License No. 21274