

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

DATE 11/2/99 JOB

JAN 5 2000

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION _____

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>41N</u> R <u>15W</u>	M3 ✓
	T <u>41N</u> R <u>14W</u>	A3
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/292
JLV Date 12/22/1999 Time 13:49:49
RECORDING FEES: 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien, in a field survey on Dec. 20, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:

August 6, 1845 J. Burt, DS set post corner of Sections 1 and 12
Cedar 19 N8W 21 Hemlock 10 S45W 33

May 15, 1980 Robert E. Schmeling, RLS reestablished corner from Soo Line Railroad survey map information.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Dec. 20, 1999 Thomas P. O'Brien, PS recovered 1" pipe at corner location. Existing witnesses verify corner position. Reset 1' pipe w/Schoolcraft County monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Schoolcraft County monument
Witnesses:
8" Cedar S30°E 3.1 to centerline tree
10" Cedar S75°W 10.7' to centerline tree
10" Cedar N30°W 23.4' to centerline tree
7" Cedar N45°E 5.0' to centerline tree
Carsonite Post North 1.0'



Signed by Thomas P. O'Brien

Date Dec. 22, 1999

Surveyor's Michigan License No. 21274