

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

**SURVEY &
REMONUMENTATION**

DATE 10/10/00 00B LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FEB 08 2001

For corners in

Schoolcraft
(County)

Located in:

Corner Code #

SECTION

- 1. Public Land Survey T42NR 13W A3
T R
T R
T R
- 2. Property Controlling in Section S T R
S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/418
JLQ Date 12/28/2000 Time 11:28:12

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Thomas P. O'Brien, in a field survey on 10/17/00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1850 Guy H. Carleton, DS "set post Cor Secs 1 & 12(42-14) Ironwood 8 N81W 35
Sugar 6 N55E 13 Beech 10 S19E 64 Maple 8 S6W 12

Sppt.25, 1900 A.C. Carpenter, Co. Surveyor " Cor. established by J. Richardson County
Sur. 96 to 98 Maple 18 N82E 44

March 1984 William F. Bowman, LLS "set by evidence of road locations, and corners
one mile east and west."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct.17, 2000 Thomas P. O'Brien, PS found 5/8" iron bar with 3" Champion cap and LS 28406
stamp as set by Bowman.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" iron bar with 3" Champion cap stamped to identify.


Witnesses:

14" red Pine S48°E 17.0'

10" Tamarack S82°W 13.88'

8" Apple N56°E 36.40'

Carsonite Post South 1.0'



Signed by Thomas P. O'Brien

Date Dec. 19 2000

Surveyor's Michigan License No. 21274