

**SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED**

**SURVEY &  
REMONUMENTATION**

**FEB 08 2001**

**DATE** 10/10/00 JOB **LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in

<u>Schoolcraft</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>13W</u>	<u>A5</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

SIGRID HEDBERG 1P  
SCHOOLCRAFT CO. REGISTER  
Page 1 of 1 LC 4/411  
JLV Date 12/28/2000 Time 11:28:08

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Thomas P. O'Brien, in a field survey on 11/7/00 ~~X19~~ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

1850 Guy H. Carleton DS set post Cor Secs 12 & 13 (42-14) Birch 12 N38E 6  
Cedar 16 S85E 26 Birch 6 S60W 25 Sugar 12 N72W 44.

March 1984 William F. Bowman, LLS " set by proportionate measure between M3(42-14) and A7."

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Nov. 7, 2000 Thomas P. O'Brien, PS found 1/2" spike and 3" Champion cap with LS 28406 stamped set in tree Stump by Bowman.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

3" Champion cap and spike stamped to identify.

Witnesses:

14" Maple S79°E 21.80'

14" Ash S40°W 23.95'

4" Maple S17°E 33.50'

16" Maple N33°W 49.62'

Carsonite Post North 1.0'



Signed by Thomas P. O'Brien

Date Dec. 19, 2000

Surveyor's Michigan License No. 21274

LIBER 4 PAGE: 411