

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

DATE 10/10/00 **LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

**SURVEY &
REMONUMENTATION**

FEB 08 2001

SECTION

For corners in

Schoolcraft
(County)

Located In:

Corner Code #

1. Public Land Survey

T 42N R 13W A7
T _____ R _____
T _____ R _____
T _____ R _____
T _____ R _____
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling
in Section

S _____
S _____

3. Miscellaneous
Property in Sec.

S _____
S _____

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/410
JLV Date 12/28/2000 Time 11:28:07

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Thomas P. O'Brien, in a field survey on 11/27/00, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1850 Guy H. Carleton DS set post Cor Sect. 13 and 24 (42N-14W) Tamarack 14 N33W 2
Tamarack 8 S45E 45 Tamarack 10 N77E 24 Fir 8 S40W 20

May 25, 1950 Carl Christensen placed a 2" x4' long iron pipe with brass cap thereon based on original witness Tamarack 8" S45° 45 lks.

Oct. 6, 1980 Robert E. Schmeling, RLS " found in place this date said monument and a 6" squared cedar post thereby."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Nov. 27, 2000 Thomas P. O'Brien, PS found a 2" iron pipe with brass cap and existing Schmeling witnesses. Stump mound S45°E 45 lks.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

2" x4' iron pipe with brass cap stamped to identify.

Witnesses:

- 12" Cedar N81°W 13.85'
- 12" Cedar N64°E 8.15'
- 16" Cedar S28°E 29.10'
- 10" Cedar S20°W 29.90'
- Carsonite Post North 1.0'



Signed by Thomas P. O'Brien

Date Dec. 28, 2000

Surveyor's Michigan License No. 21274

LIBER N PAGE: 410