

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

**SURVEY &
REMONUMENTATION**

DATE 10/10/00 **LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

FEB 08 2001

For corners in

Schoolcraft

(County)

Located In:

Corner Code #

SECTION

1. Public Land Survey

T 42N R 13W

A8

SIGRID HEDBERG

1P

SCHOOLCRAFT CO. REGISTER

Page 1 of 1

LC 4/416

JLO Date 12/28/2000

Time 11:28:11

2. Property Controlling
in Section

S

T R

3. Miscellaneous

S

T R

Property in Sec.

S

T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Thomas P O'Brien, in a field survey on 11/27/00, ~~19~~ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

April 1851 Algernon Merryweather. DS destroyed Guy H Carleton post and witnesses in remeasurement.

March 1984 William F. Bowman LLS "set by proportionate measure on line between M7 (42-14) and A9."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Nov.27, 2000 Thomas P. O'Brien PS found 5/8" iron bar with 3" Mead cap and LS 28406 stamp as set by Bowman.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" iron bar with 3" Mead cap stamped to identify.

Witnesses:

12" Cedar N46°EW 39.65'

8" Cedar S69°E 39.10'

12" Cedar S72°W 32.55'

4" Balsam N13°W 13.50'

Carsonite Post North 1.0'



Signed by Thomas P. O'Brien

Date Dec.27, 2000

Surveyor's Michigan License No. 21274

LIBER 4 PAGE 416