

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

**SURVEY &
REMONUMENTATION**

DATE 10/10/00 JOB

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

FEB 08 2001

For corners in

Schoolcraft
(County)

Located In:

Corner Code #

SECTION

1. Public Land Survey

T 42N R 13W A11
 T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

SIGRID HEDBERG 1P
 SCHOOLCRAFT CO. REGISTER
 Page 1 of 1 LC 4/409
 JLV Date 12/28/2000 Time 11:28:06

2. Property Controlling
in Section

S _____
 S _____

3. Miscellaneous
Property in Sec.

S _____
 S _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Thomas P. O'Brien, in a field survey on 11/27/00, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1850 Guy H. Carleton DS set post Cor to Sect. 25 and 36 (42N-14W)
 Spruce 10 S65W 30 Cedar 14 N49W 24 Cedar 10 N20E 37 Cedar 16 S13E 36

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Nov. 27, 2000 Thomas P. O'Brien PS set corner by single proportionate measure between A10 and A13.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Schoolcraft County monument stamped to identify.

Witnesses:

- Centerline rail S0°41'02"W 33.65'
- 10" Tamarack S60°W 10.0'
- 6" Tamarack N49°E 25.95'
- 4" Tamarack N68°W 15.10'
- Carsonite Post North 1.0'



Signed by Thomas P. O'Brien

Date Dec. 28, 2000

Surveyor's Michigan License No. 21274

LIBER 4 PAGE: 409