

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 42-43 N. R. 14W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Section Corner for Sections 31-6, also township corner for  
Towns 42-43 North, Range 14 West.

CORNER MONUMENT 1" Pipe with 4" Brass Cap.

DATE MONUMENT PLACED AND WITNESSED 5-23-61

WITNESSES TO CORNER..... 9" Jack Pine (S6 NBT) N53°E 46½ links



10" Jack Pine (S31 NBT) S35°E 124 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established 1.65 chains (record distance) North of Township Corner for towns 42-43 N, R15W.

Note: Township Corner 42-43N, R15W lies 1.65 chains South of this Corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE December 29, 1961  
REGISTERED LAND SURVEYOR  
Billy D. Buckler