

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42 & 43 N. R. 14W

Schoolcraft COUNTY

DESCRIPTION OF CORNER 1/4 Corner between 34 T43N R14W


3 T42N R14W

CORNER MONUMENT 1" Iron pipe with 4" brass cap.

DATE MONUMENT PLACED AND WITNESSED 5-9-61

WITNESSES TO CORNER..... 12" Hard Maple (NBT) N55°E 133 links

9" Hard Maple (NBT) S78°E 128 links



AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by single proportionate measurement between Section Corner $\frac{1}{2}$ mile west and $\frac{1}{4}$ corner 2 miles east and in old E & W fence line.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler

REGISTERED LAND SURVEYOR

Billy D. Buckler

DATE December 28, 1961