

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 42-43 N.R. 14W


Schoolcraft COUNTY

DESCRIPTION OF CORNER  $\frac{1}{4}$  Corner between Sections 4-33

CORNER MONUMENT 1" Pipe with 4" Brass Cap.

DATE MONUMENT PLACED AND WITNESSED 5-3-61 with D. St. Ours

WITNESSES TO CORNER..... 8" Cedar ( $\frac{1}{4}$ S NBT) N85°E 16 links



6" Cedar ( $\frac{1}{4}$ S NBT) S35°W 19 $\frac{1}{2}$  links

6" Cedar ( $\frac{1}{4}$ S NBT) N50°W 43 $\frac{1}{2}$  links

AND

CIRCLE CORNER REGISTERED

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner was placed at old fence corner. Found old blazes at Corner. Distance East 40.08 chains to Section Corner and West 40.18 chains to Section Corner. Found old 20" Cedar log which was moved in road construction. Unable to identify any marks on this Cedar but believe it to be an original bearing tree. Corner lies on South side of road.

**SURVEYOR'S SEAL**

SIGNED *Billy D. Buckler* DATE December 28, 1961  
REGISTERED LAND SURVEYOR  
Billy D. Buckler