

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42 N.R. 14-15 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 1, 12, 6, 7

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 5/10/61 with Duaine St. Ours.

WITNESSES TO CORNER... 10" J. Pine (S 1 NBT) N 45 deg. W 17 Links



8" J. Pine (S 6 NBT) N 33 deg. E 22 Links

8" J. Pine (S 7 NBT) S 40 deg. E 38 Links

AND

8" J. Pine (S 12 NBT) S 5 deg. W 45 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from remains of two N. Pine B.T.'s bearing N 70 deg. W, 24 Links and S 75 deg. W, 43 Links, both stumps badly burned. Found Notch on SW Stump. Distance North and East to Stream fits very good. Corner lies on E-W Jack Pine Ridge. Corner found by Art Enger, Assistant District Forester.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 9/15/61
REGISTERED LAND SURVEYOR
/Billy D. Buckler