

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42-43 NR. 13-14W.

----- Schoolcraft ----- COUNTY

DESCRIPTION OF CORNER ----- Cor. of Secs: 1-6-31-36 also township cor. -----

DESCRIPTION OF CORNER MONUMENT ----- 1" Pipe with 4" Brass Cap -----

WITNESSES TO CORNER ----- 9" Cedar (S31 NBT) N51^oE 18 Lks. -----

----- 7" Cedar (S36 NBT) West 8 Lks. -----

----- 8" Cedar (S6 NBT) S32^oE 31 Lks. -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced cor. at old wood post, found Cedar stump bearing N60^oE
24 Lks. with old rotted face and marks on overgrowth. Position
checks with stream north and east. Found by Forestry Division
Survey Crew while making retracement survey of twp. Cor. lies
in swamp. Cor. placed and wit. 1/27/59.

SURVEYORS SEAL

Billy D. Buckler
SIGNED ----- Billy D. Buckler ----- DATE 7/31/59 -----
REGISTERED LAND SURVEYOR