

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42-43 N. R. 14 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 1, 2, 35, 36

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 5/9/61

WITNESSES TO CORNER... 10" Balsam (S 2 NBT) S 25° W 11 1/2 Links



5" Balsam (S 1 NBT) S 88° E 11 1/2 Links

7" Spruce (S 35 NBT) N 71° W 38 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by single proportionate measurement and in line between 1/4 corner 1/2 mile East and 1/4 Corner 1 1/2 miles West. No original evidence.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 9/15/61
REGISTERED LAND SURVEYOR
Billy D. Buckler