

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42-43 N. R. 14 W


Schoolcraft COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 2, 3, 34, 35

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 5/9/61

WITNESSES TO CORNER... 12" Tamarack (S 2 NBT) S 08° E 38 1/2 Links



10" Cedar (S 35 NBT) N 59° E 24 Links

6" Cedar (S 3 NBT) S 76° W 15 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by single proportionate measurement between 1/4 corner 1/2 mile west and Section Corner 1 mile East. No original evidence.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 9/15/61
REGISTERED LAND SURVEYOR
Billy D. Buckler