

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES
LAND CORNER RECORD

Schoolcraft COUNTY


T 42 N R's 14 & 15W

DESCRIPTION OF CORNER Section corner for sections T42N 12/7 T42N
R15W 13/18 R14W

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 11/5/69, F. J. Bray with M. Burnis

WITNESSES TO CORNER..... 8" H. Maple (S.18) (NBT) S 89° E, 38 1/2 links



7" S. Maple (S.12) (NBT) N 41° W, 21 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed on line and the single proportioned measurement between section corners one mile to north and to south. Corner checks fairly well with bay^o crossings to north, south, east, and west.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED Frank J. Bray DATE 11/19/69
REGISTERED LAND SURVEYOR
Frank J. Bray

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68