

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES
LAND CORNER RECORD

Schoolcraft COUNTY


T 42 N R's 14 & 15W

DESCRIPTION OF CORNER S 1/16 corner for sections T42N R15W 13/18 T42N R14W

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 11/15/69 F. J. Bray with M. Burnis

WITNESSES TO CORNER..... 12" Cedar (S 1/16) (BT) S 87° W, 78 links



24" Dead Hemlock (S 1/16 BT) N 70° W, 08 links

5" H. Maple (S 1/16) (BT) N 49° E, 21 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed midway and on line between section corner to south and 1/4 corner to north.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED Frank J. Bray
REGISTERED LAND SURVEYOR
Frank J. Bray

DATE 11/19/69

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68