

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

SURVEY &
REMONUMENTATION

NOV 2 1 1996

COMMISSION

DATE 9/13/96

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft <small>(County)</small>	Located In:	Corner Code #/
1. Public Land Survey	T 42 N R 15 W T 42 N R 14 W T ___ R ___ T ___ R ___	M-5 A-5 ✓
2. Property Controlling in Section	S ___ T ___ R ___ S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___ S ___ T ___ R ___	

Received & Filed this 30 day of
Oct 1996 at 11:37 AM
Sigrid I. Hedberg
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												X
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Thomas P. O'Brien, in a field survey on April 3, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-5 (S.E. Corner Sec. 12)
Sept. 10, 1850 Algernon Merryweather D.S. set corner post.
Birch 26 in. S60W 23 links Birch 12 in. N52W 45 links

April 20/51 Algernon Merryweather D.S. Corner 7&18.
Sugar 10 S50E 11 lks. Birch 20 N10E 43 "

SURVEY &
REMONUMENTATION
DEC 1 6 1996
COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-5 Nov. 5, 1969- Franf J. Bray, RLS set a 1" iron pipe with 4" aluminum cap. " On line and at the single proportioned measurement between section corners 1 mile to the North and to the South."

April 3, 1996- Thomas P. O'Brien, P.S. recovered a 1" pipe with 4" aluminum cap as set by Frank J. Bray on Nov. 5, 1969.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5 Found Dept. of Cons. 1" pipe with 4" aluminum cap stamped to identify.

Witnesses: Fd. 7" Maple- N41°W - 21 lks. (8' Dead Stub)
8" Cedar- N 7°W - 97.50' NBT
10" Cedar- N72°W - 77.60' NBT
12" Cedar- S12°W - 89.05' NBT
12" Cedar- S32°E - 65.10' NBT



Signed by Thomas P. O'Brien Date April 3, 1996

Surveyor's Michigan License No. 21274

LIBER 4 **PAGE:** 63