

**SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED**

**DATE** Mat 12, 1995 **LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

JAN 30 1996  
COMMISSION

For corners in

Schoolcraft (County) Located In: Corner Code #

1. Public Land Survey T 42 N R 15 W M-7  
T 42 N R 14 W A-7 ✓  
T R  
T R

2. Property Controlling S T R  
in Section S T R

3. Miscellaneous S T R  
Property in Sec. S T R

Received & Filed this 6 day of  
Dec 19 95 at 4:44 A M  
Sigrid I. Hedberg  
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Thomas P. O'Brien, in a field survey on Nov. 7, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

M-7 (S.E Corner Sec. 13)  
Sept. 10, 1850 Algernon Merryweather D.S. set corner post.  
Cedar 7 in. N70W 2 links Spruce 10 in. S62W 65"  
  
April 19/51 Algernon Merryweather D.S. Corner 18&19 West Boundary  
Cedar 16 in. N35E 26 lks. Tamarack 16" S88E 14"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-7 Jan. 8, 1957 Billy D. Buckler, RLS found 2 1/2" iron pipe with brass cap set by Carl Christensen.  
  
Oct. 19, 1994 Thomas P. O'Brien, PS recovered iron pipe w/brass cap set by Carl Christensen from 2 original witness trees "Cedar 16in. N35E 26 lks. Tamarack 16" S88E 14" as noted in County Surveyors book.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7 2" iron pipe w/2 1/2" brass cap stamped to identify by "CC".  
Witnesses: (previous witnesses by B. Buckler have been cut.)  
10" Cedar N30°W 14.45'  
12" Cedar N82°W 31.60'  
6" Cedar S31°W 19.65'  
Post South 1.5'



Signed by Thomas P. O'Brien, PS Date Dec. 4, 1995

Surveyor's Michigan License No. 21274