

**SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED**

SURVEY &  
RECORDATION

JAN 30 1996

DATE Dec. 7, 1995

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Schoolcraft <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>42 N</u> R <u>15 W</u>	<u>M-11</u>
	T <u>42 N</u> R <u>14 W</u>	<u>A-11</u> ✓
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Received & Filed this 21 day of  
Dec. 1995 at 2:32 PM  
Sigrid I. Hedberg  
Schoolcraft Co. Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Thomas P. O'Brien, in a field survey on Dec. 27, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

M-11 (S.E. Corner Sec. 25)  
Sept. 9, 1850 Algernon Merryweather D.S. set corner post.  
Cedar 14 in. N85W 20 links Birch 8 " S28W 43 "  
  
April 17/51 Algernon Merryweather D.S. Corner 30&31.  
Cedar 9 in. N37E 26 links Birch 10" S28E 13 "

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11 Dec. 29 # 1993 Thomas P. O'Brien, PS recovered 1/2" iron bar with plastic PS cap # 28406. Testimony of William F. Bowman and measured distances verify corner was set by single proportionment measurement between M7 and M12. Replace 28406 iron bar with Schoolcraft County monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M11 Schoolcraft County monument stamped to identify.  
Witnesses:  
10" Cedar N73°W 74.50'  
Power Pole N10°W 175.65'  
Power Pole S30°W 128.91'  
Cedar Post East 9.50'  
Centerline county road West 14.70'



Signed by Thomas P. O'Brien Date Dec. 20, 1995  
Surveyor's Michigan License No. 21274