

SCHOOLCRAFT COUNTY PEER GROUP APPROVED

JAN 4 5 2000

SECTION _____

DATE 12/15/99

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Schoolcraft

(County)

Located In:

Corner Code #

1. Public Land Survey

T 41N R 14W

C1

T 42N R 14W

C13 ✓

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

SIGRID HEDBERG

1P

SCHOOLCRAFT CO. REGISTER

Page 1 of 1

LC 4/326

JLV Date 12/30/1999

Time 13:57:13

RECORDING FEES:

9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Thomas P. O'Brien, in a field survey on 12/23, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1851 Algernon Merryweather, DS Remeasurement NBT's Tamarack 10 N32E 21 links Balsam 10 N12W 14 Oct.13, 1998 Keith R. Waters, PS found a 2" iron pipe at the approximate corner of a pasture. Accepted corner as found and placed a 1/2" rebar with 33142 cap in the center of found pipe.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DEc.23, 1999 Thomas P.O'Brien, PS recovered 2" pipe as found by Keith R. Waters, PS and verified by existing witnesses and distances to B1. Reset 2" pipe with Schoolcraft County monument stamped to identify.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Schoolcraft County monument
Witnesses:
7" Cedar N42°E 26.38'
7" Cedar N80°E 41.23'
5" Twin White Birch S43°E 21.50'
8" Aspen S52°W 27.44'
Carsonite Post South 1.0'

Thomas P. O'Brien

Signed by Thomas P. O'Brien

Surveyor's Michigan License No. 21274

Date DEc.30, 1999

