

SCHOOLCRAFT COUNTY
PEER GROUP APPROVED

SURVEY &
REMONUMENTATION

FEB 08 2001

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

DATE 10/10/00 JOB
For corners in

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/375
JLV Date 12/19/2000 Time 11:53:21

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T 42N R 14W	G1 ✓
	T 43N R 14W	G13
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien, in a field survey on 10/30/00, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Oct. 20, 1850 Algernon Merryweather, DS section corner Sections 3, 4
Sugar 16 in S73W 55 links Sugar 9 in S33E 15 links Sugar 16 in N47E 45 birch 28 N60W 22

Dec. 28, 1961 Billy D. Buckler, RLS "This corner was replaced 50 links south of fence corner and in intersection of roads to South, East and West. Position checks with good corners to West.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct. 30, 2000 Thomas P. O'Brien, PS found 3/4" iron bar with illegible cap. Accepted iron bar and reset with Schoolcraft County monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Schoolcraft County monument stamped to identify.

Witnesses:
26" Maple N23°E 29.70'
Road Sign S11°E 43.83'
14" Maple N25W 43.47'
24" Maple S56°W 69.38' - existing Buckler BT - Good distance.
Carsonite Post N5°E 30.0'



Signed by Thomas P. O'Brien
Surveyor's Michigan License No. 21274

Date Dec. 12, 2000