

SCHOOLCRAFT COUNTY
PEER GROUP APPROVED

SURVEY &
REMONUMENTATION

FEB 08 2001

DATE 10/10/00 DOB LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Schoolcraft Located In: Corner Code #
(County)

1. Public Land Survey T 42N R 14W G3
T ___ R ___
T ___ R ___
T ___ R ___

2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ R ___

3. Miscellaneous S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/369
JLV Date 12/19/2000 Time 11:53:17

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien, in a field survey on 10/31/00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

April 11, 1851 Algernon Merryweather, DS set Section Corner 3,4,9,10 Sugar 10 in N70E 5 links Beech 6 in S40W 15 links

Nov.22, 1975 Thomas P. O'Brien, PS "found 1/2" iron bar raised to surface with 1/2" iron bar with 21274 cap.

June 9, 1976 Herbert L. Fluharty "fd. 1/2" iron in centerline 4-way intersection.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct.31, 2000 Thomas P. O'Brien recovered iron bar reset from existing witnesses 5/00. Reset with Schoolcraft County monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Schoolcraft County monument stamped to identify.

Witnesses:

20" Twin Spruce N49°E 46.80'

24" Twin Spruce N72°E 81.03'

Gate Post S19°E 37.48'

Power Pole S57°W 44.65'



Signed by Thomas P. O'Brien

Date Dec. 11, 2000

Surveyor's Michigan License No. 21274

LIBER 4 PAGE 369