

**SCHOOLCRAFT COUNTY  
PEER GROUP APPROVED**

DATE 10/10/00 JOB

**SURVEY &  
REMONUMENTATION**

FEB 08 2001

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION \_\_\_\_\_

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>14W</u>	<u>G4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

SIGRID HEDBERG 1P  
SCHOOLCRAFT CO. REGISTER  
Page 1 of 1 LC 4/392  
JLO Date 12/19/2000 Time 11:53:31

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Thomas P. O'Brien, in a field survey on 11/6/00, MSX do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9	X	10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

April 11, 1851 Algernon Merryweather, DS set 1/4 post in windfall.

Nov. 22, 1975 Thomas P. O'Brien, PS "set R/R spike in centerline trail opposite fence line to West. Dimensions check well North and South."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Nov. 6, 2000 Thomas P. O'Brien, PS found 1/2" iron bar reset from existing witnesses in 5/00. Reset with Schoolcraft County monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Schoolcraft County monument stamped to identify.

Witnesses:

16" Maple N38°W 38.0'

14" Maple S26°E 34.43'

30" Maple S87°E 7.63'

10" Twin Maple S54°W 31.58'


Carsonite Post N85°W 25.0'

*Thomas P. O'Brien*

Signed by Thomas P. O'Brien

Surveyor's Michigan License No. 21274

Date Dec. 11, 2000



LIBER 4 PAGE: 392