

**SCHOOLCRAFT COUNTY
PEER GROUP APPROVED**

DATE 10/10/00 DOB

**SURVEY &
REMONUMENTATION**

FEB 08 2001

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Schoolcraft (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>14W</u>	<u>G5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

SIGRID HEDBERG 1P
SCHOOLCRAFT CO. REGISTER
Page 1 of 1 LC 4/393
JLV Date 12/19/2000 Time 11:53:32

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas P. O'Brien, in a field survey on 11/6/00 ~~xxx~~ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5			4		3		2			1	
3													
4	7	8			9		10		11			12	
5													
6	13	17			16		15		14			13	
7													
8	19	20			21		22		23			24	
9													
10	30	29			28		27		26			25	
11													
12	31	32			33		34		35			36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

April 11, 1851 Algernon Merryweather, DS set corner sections 9,10,15,16 Balsam 6 in N78E 6 links Cedar 7 in S80W 37 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Nov.6, 2000 Thomas P. O'Brien, PS set corner using North and South proportionate distance and centerline of North and South trail road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Schoolcraft County monument stamped to identify.

- Witnesses:
10" Maple N6°E 7.15'
6" Spruce N57°W 19.17'
4" Apple N88°W 11.25'
8" Cedar S31°E 75.65'
Carsonite P0st S5°W 1.0'



Signed by Thomas P. O'Brien
Surveyor's Michigan License No. 21274

Date Dec.11, 2000